



Parks & Open Space Advisory Committee January 22, 2015

Watershed Recovery



Emergency Response



Immediate Threat Assessment and Mitigation



Long-Term Vision

Watershed Master Plans




Future Creek Projects

Funding and Implementation

Agenda

- Overview: Comprehensive Creek Planning Initiative
 - Plan development
 - Outcomes
- Parks and Open Space
- Next steps for Watershed Recovery
 - o Plan use
 - Project implementation
- Public Comment
- Planning Commission Feedback

Boulder County Watersheds



Comprehensive Creek Planning Initiative

- Initiated to ensure county-wide view of creek recovery and restoration
- Began with community meetings to identify needs
- Moved to high-hazard debris removal and mitigation projects
- Prepared for and transitioned to watershed-level master planning process
- Master plans complete in December 2014



Watershed Master Plans

Little Thompson River



Little Thompson Watershed Restoration Master Plan







COLORADO Colorado Water Conservation Board Department of Natural Resources




Watershed Master Plans

St. Vrain Creek

St. Vrain Creek Watershed Master Plan

PREPARED BY







Watershed Master Plans

Left Hand Creek

LEFT HAND CREEK WATERSHED MASTER PLAN





Watershed Master Plans

Fourmile Creek

Fourmile Creek Watershed Master Plan







COLORADO Colorado Water Conservation Board Department of Natural Resources

DRAFT REPORT, NOVEMBER 2014



Watershed Master Plans

Coal Creek (Upper Reaches)









Centennial, CO 80112 303-221-0802 www.iconeng.com





Restoration Master Plan

Upper Coal Creek Watershed

November 2014

Jefferson and Boulder Counties



Watershed Master Plans Enabling Flood Recovery through Watershed Planning

- Partnerships
 - Coalition partners
 - Community members & landowners
 - Stakeholder interests

Resources

- County: Staffing and funding, \$300K
- State: Guidance and funding
 - CWCB Master Plan Grant, \$700K
 - CDBG-DR Planning Grant, \$80K
 - CWCB Stream Restoration Grants*

*Funding needed for project implementation, including local match













Environmental Scientists and Engineers, LLC



Community Engagement

- 1 project video produced
- 15 community meetings with over 575 total participants
- 3,593 postcards sent announcing the master plan process and kick-off community meetings
- 10 presentations at meetings, conferences, and workshops
- 13 press releases sent
- 16 external emails with updates and announcements on master plans

Information Clearinghouse

/www.bouldercounty.org/flood/property/pages/creeks.aspx D + C × 😁 Creek Planning & Recovery ×

h ★ 2

File Edit View Favorites Tools Help

🚕 🔄 InsideBC Home 🗿 Kronos Workforce Central... 🖮 Boulder County 🖮 Creek Planning & Recovery 🖮 Floodplain Management

Flood

Restoration & Repair Self-Report Property Damage Assessment

Septic Systems Roads Videos & Photos

Families & Adults Open Space & Recreation Property & Land Roads & Transportation Environment Safety & Law Licenses, Permits & Records Creek Planning & Recovery Assistance Boulder County's Comprehensive Creek Planning Initiative (CCP) is helping the county move forward with long-term creek recovery by initiating watershed-level master planning processes throughout the county. Master plans will assist in rebuilding efforts by Cleanup, Health & Safety Community Resiliency providing post-flood analysis of flows, facilitating key decisions about creek alignment, and identifying actions for stream restoration and flood risk management. The master planning process will be an open and collaborative effort among public Contacts agencies, property owners, ditch companies, stakeholders, and the public. Emergency Preparedness FAQs Forms News Rebuilding & Restoration Assessor Valuation & Taxes Comprehensive Creek Planning Initiative Creek Planning & Recovery Flood Rebuilding & Permit Hazard Mitigation Review Permits Private Roads, Culverts & Bridges



For more information on the r

More information on each of the master plans can be found at the links below:


Master Plan Pages				
Boulder Creek (Lower Reaches)	Left Hand Creek			
Coal Creek (Lower Reaches) and Rock Creek	Little Thompson River			
Coal Creek (Upper Reaches)	South Boulder Creek			
Fourmile Creek	St. Vrain Creek			

Events Calendar

For a list of all events for the Comprehensive Creek Planning Initiative, please see the CCP Events Calendar,

News & Presentations

- Colorado Watershed Symposium Presentation, July 2014 (2 MB)
- Boulder County Watershed Coalitions Presentation, June 2014 (3 MB)
- Post-Flood Planning in Boulder County 3
- Update Presentation to Planning Commission, May 2014 (2 MB)
- Comprehensive Creek Planning Initiative Moves Forward, February 2014
- Update Presentation to Planning Commission, January 2014 (2 MB)
- Community Outreach Meeting Presentation. December 2013 (740 KB)
- Commissioners' Study Session on the Stream Planning Initiative, November 2013





Watershed Master Plans

Plan Outcomes

Multidisciplinary technical assessment of current watershed conditions, including:

- Ecological Assessment
- Geomorphic Assessment
- Flood Risk Assessment
- Channel Migration Zone Analysis


Ecological Assessment

St. Vrain Creek

Poor



Recommendations: Consider opportunities for improved meanders, habitat, vegetation, etc.; need to create more complexity within the channel



No further management recommended

Geomorphic Assessment

Left Hand Creek



Tight bedrock pinch led to stripping of alluvium in James Canyon, ultimately destroying the roadway and the pre-flood channel.


Poor

In tact section of lower Left HandCreek (on BoCo Open Space). Thisreach largely in tact due tofunctioning, connected floodplain.





Watershed Master Plans



Project Descriptions

NEIGHBORHOOD: Boulder County SHEET: 41 STATION: 1299+00 to 1333+00 RESTORATION RECOMMENDATIONS: 1308+00 to 1326+00

Aerial photos of pre-flood conditions and anecdotal information indicate this reach had a moderately dense vegetated riparian corridor, ranging from 150 feet directly along the river corridor to more than 550 feet wide in areas with expanded floodplain surfaces. The vegetation is comprised primarily of cottonwoods, some willows, and other riparian species, many of which were torn out during the flood. Flood flows caused considerable scour of the floodplain and overbank surfaces in



some areas, including significant lateral channel migration in the large bend near Sta 1325+00 and Sta 1302+00. Due to the significant scour upstream, including significant sediment and debris transported through the upstream canyon, large sediment deposits, including coarse material, also exist in this area.

The 2013 Flood caused many of the significant channel bends to erode laterally into overbank surfaces that have primarily been used as cropland. Sinuosity of the channel was also generally reduced as flood flows scourced a more direct flow path along the floodplain.

Although significant geomorphic changes have occurred in this reach as a result of the 2013 Flood, much of the current channel and floodplain is relatively stable, and expected to recover without significant restoration activities. However, there are some overbank areas that require some fill and reclamation along with some bank stabilization. Seeding or planting of the reworked channel banks would help accelerate vegetation recruitment.

The Boulder Larimer (Ish) Irrigation Ditch diversion structure has been reconstructed, and significant channel reconstruction both upstream and downstream of the diversion dam has occurred.

RESTORATION RECOMMENDATIONS

- 1. Stabilize right bank between Sta 1298+00 and Sta 1309+00 to protect irrigation ditch.
- 2. Stabilize left bank near Sta 1302+00.
- Create and/or refine low-flow channel near Sta 1320+00 to improve conveyance and sediment transport in this area. Effects of low-flow channel will be limited at downstream end due to Boulder Larimer (Ish) Irrigation Ditch diversion dam.
- 4. Stabilize banks near Sta 1324+00.
- Develop low-flow channel below diversion dam and grade adjacent floodplain surface (much of this work has already occurred).

OPINION OF PROBABLE COST

Item Description	Unit	Unit Price	Sta 1308+00 to Sta 1326+00 Sheet 40 and 41		
			Mob/Demob	LS	\$32,400
Dewatering	LF	\$ 14	2400	\$	33,600
Create/refine Low Flow Channel	LF	\$ 27	1400	\$	37,800
Excavate, Grade Low Flow Channel (capacity)	LF	\$ 48		\$	-
Grade Control	EA	S -		\$	-
Grading	AC	\$ 8,000	0	\$	-
Floodplain Stabilization	AC	\$ 8,100	2	\$	16,200
Lowering and Grading	AC	\$32,300		\$	
Point Bar Creation	LF	\$ 5	1400	\$	7,000
Bank Stabilization, Level 1	LF	\$ 110		\$	23
Bank Stabilization, Level 2	LF	\$ 75	1000	\$	75,000
Bank Stabilization, Level 3	LF	\$ 45	0	\$	-
Land Reclamation Fill	AC	\$20,200		\$	-
Upper Bank Stablization, Level 1	LF	\$ 25		\$	-
Upper Bank Stablization, Level 2	LF	\$ 15		\$	-
Upper Bank Stablization, Level 3	LF	\$ 5		\$	
Seeding	AC	\$ 5,000	10	\$	50,000
Temporary irrigation and weed management	LS	\$22,800	1	\$	22,800
Site Specific	LS	s -		\$	-
SUBTOTAL				\$	274,800
Contingency, 15% of subtotal				\$	41,200
Permitting , 2.5% of subtotal	1			\$	6,900
Design, plans, specification, contract administration,	15%			\$	41,200
Supervision & Administration, 10%				\$	27,500
TOTAL		1		\$	392,000







Conceptual Designs



Figure 28. Graphical example of existing crossing constructed with low-flow channel that facilitates aquatic organism passage and sediment transport.





Figure 7.4 Large Woody Debris Bank Protection Detail*





Watershed Master Plans

Project Prioritization

Fourmile Ćreek Master Plan

Tier 1 - Projects reducing flood risk due to post-flood conditions

Reach 1 – Removal of Sediment aggradation from the channel near Mile Marker 1.1

Reach 1 – Fourmile Creek restoration project (CWCB Grant)

Reach 3 – Assessing the stability of existing walls and modifying if necessary

Reach 3 – Filling and revegetating avulsion areas

Reach 3 – Installing debris racks and stabilizing the banks of Ingram Gulch Reach 4 – Removal of sediment aggradation from the channel and floodplain near Mile Markers 5.1, 5.8, and 6.3

Reach 4 – Removing a debris jam in a high avulsion risk area near Mile Marker 7.7

Tier 2 - Projects that improve stream stability and promote ecological recovery

All Reaches – Low flow channel restoration

All Reaches – Increasing in-stream habitat

All Reaches – Revegetation

Reaches 1, 3, and 4 – Bank Protection

Reach 3 – Relocating Fourmile Creek in the vicinity of Salina Junction

Reach 4 – Removing a temporary berm near Mile Marker 7.2 and bank protection

Tier 3 - Projects that affect areas with low risk to infrastructure

Reach 2 – Filling the pre-flood channel to reduce avulsion risk



Watershed Master Plans

Cost Estimates

- Top priority projects
 - o St. Vrain
 - o Left Hand
 - o Fourmile

- \$68 million* \$20 million** \$2.6 million*
- Floodplain management recommendations and cost estimates
 - Studies and remapping \$1.6 million

*Cost estimates for all Tier 1 projects with unmet needs **Cost estimates for all of the top 5 projects with unmet needs



Plan Use

- Conceptual
 - Framework and guidance for recovery actions
 - o Informed by scientific data
 - Next steps of further planning, design
- Funding tool
- Communication and organizing tool



Long-Term Recovery

Project Implementation

- Projects could be completed by:
 Individual property owners
 - o Groups of neighbors
 - Watershed Coalitions
 - Government agencies
 - Non-governmental agencies
 - Cooperative efforts
- Private property owners will need to participate/give approval for any projects on their property

Project Funding: CDBG-DR Round 2

Two Programs for Creek Recovery (DOLA/CWCB)

- Watershed Resiliency
- Planning Resiliency

January

Planning program: Projects (up to 30% design) Planning program: Staff

Watershed program: Watershed Coordinators

<u>March</u>

Watershed program: Small scale or pilot projects <u>November</u> Watershed program: Large projects



Project Funding: CDBG-DR Round 2

County Applications- January

- Floodplain program staff
- Floodplain studies and map updates
- Creek recovery staff
- Project design, to prepare for November applications
 - o South St. Vrain Creek (Hall Meadows)
 - $_{\odot}\,$ St. Vrain breaches 1 and 2
 - o St. Vrain breaches 5-9
 - Left Hand Creek and Fourmile Creek stream restoration (roadway design integration)



Next Steps: Creek Recovery and Restoration Program Activities (Winter-Spring)

- Complete county adoption of master plans
- Continue participation in Coalitions
- Complete January and March CDBG-DR Round 2 funding applications
- Initiate project designs (30%) by department staff, when funding secured
 - o Parks & Open Space
 - o Transportation
- Pursue additional funding for project implementation
 - Projects considered on a case-by-case basis
 - Dependent on resource availability
- Complete CWCB Watershed Planning grant activities
 - Lower Boulder Creek Master Plan (UDFCD)
- Continue communication and outreach activities



Vision

Watershed Master Plans

Plan Adoption

Feedback on Plans

- Planning Commission
- POSAC

January 21 January 22

Adoption

• BOCC

February 26

Julie McKay Phone: 720-564-2662 Email: jmckay@bouldercounty.org Website: www.BoulderCountyCreekPlan.org

St. Vrain Creek Watershed Master Plan

PREPARED BY












PREPARED FOR


The St. Vrain Creek Coalition

NOVEMBER 25, 2014



PLANNING AREA DESCRIPTION





St. Vrain Creek Watershed Master Plan

- Worked with:
 - St. Vrain Creek Coalition
 - Michael Baker Jr., Inc. Consulting Team
- Regular and one-on-one meetings
- Provided property and damage assessment information
- Input and comments throughout process



Management Plans and Policies

- Boulder County Comprehensive Plan Environmental Resources Element (Boulder County 2014)
- St. Vrain Creek Corridor Open Space Management Plan (2004)
- St. Vrain Trail Master Plan (2004)
- Pella Crossing and Marlatt Open Space Recreation and Visitor Use Plan (2003)
- North Foothills Management Plan (Hall Ranch and Heil Valley Ranch)
- Parks & Open Space Water Policy
- St. Vrain Creek Greenway Master Plan (City of Longmont 2001)

Assessments

- Riparian Inventory & Assessment Boulder County Parks & Open Space (2009)
- Survey of Critical Biological Resources in Boulder County, Colorado (2009)
- Environmental Assessment South St. Vrain Creek (2000)
- Pella West Hydrology Study (2009)
- Hall Ranch Meadows Natural Resource Assessment (2005)
- Braly Property Rapid Assessment Report (2001)
- Habitat Assessment and Survey Report Portions of Gage-Marlatt Open Space
- Keyes Property Rapid Assessment Report (2002)
- Ramey Homestead Property Rapid Environmental Site Assessment (2001)
- Resource Assessment Report Custode Property (2000)

St. Vrain Creek – Significant Resources

- St. Vrain Creek Corridor Open Space Management Plan
 - Highlighted significant resources along creek designated as "Sensitive"
- Env. Resource Element Critical Wildlife Habitat
 - Well-developed complex cottonwood-willow gallery forest
 - Most important native fisheries along Front Range
 - Numerous species of special concern
- Riparian Inventory & Assessment Boulder County Parks & Open Space (Biohabitats 2009)
 - 6 out of 14 reaches "High Functioning", remaining 8 = "Moderate Functioning"


Special Status Species

- Preble's Meadow Jumping Mouse (FT)
- Ute's Ladies Tress Orchid (FT)
- Colorado Butterfly Plant (FT)
- Plains Topminnow
- Common Shiner (ST)
- Iowa Darter (state SSC)
- Stonecat (state SSC)
- Bald Eagle
- Great Blue Heron Rookery
- + 54 other potential special status species



REACH 3 U.S. 36 TO AIRPORT ROAD

St. Vrain Creek Watershed Master Plan




7-13


Settore low flow channel and loodplain bench in new align:

Low-flow Channel Reconstruction Bank Protection / Stabilization Habitat Restoration


ST. VRAIN CREEK

CONCEPTUAL PLAN





St. Vrain Creek Watershed Master Plan




7-16


Low-flow Channel Reconstruction Bank Protection / Stabilization Habitat Restoration


Recommendations and Conceptual Design Strategies

ST. VRAIN CREEK CONCEPTUAL PLAN

REACH 4B SOUTH ST. VRAIN / HALL MEADOWS







REACH 1 SANDSTONE RANCH/PESCHEL

Work with City of Longmont Natural Channel Design and Floodplain Bench Bank Protection / Stabilization Habitat Restoration

Prioritization

Tier 1 – Projects reducing flood risk due to post-flood conditions

- Reach 3 Breach Repairs
- Reach 4b Hall Meadows/South St. Vrain
- **Tier 2** Projects that improve stream stability and promote ecological recovery
 - Reach 3 Stream Restoration

Tier 3 – Projects that affect areas with low risk to infrastructure


○ Reach 1 – Sandstone Ranch (Peschel)

Little Thompson—Parrish 2





Fourmile Creek Flood Recovery Project



Parks and Open Space Project Sites-Lefthand Creek

