



ADDENDUM #2
Transportation
Gold Run Road Permanent Repairs and Gold Run Stream Restoration
BID # 6666-17

July 11, 2017

The attached addendum supersedes the original Information and Specifications regarding BID # 6666-17 where it adds to, deletes from, clarifies or otherwise modifies. All other conditions and any previous addendums shall remain unchanged.

Please see below for the Traffic Management Plan document Dropbox link:

<https://www.dropbox.com/s/c39eprv6ymkg94b/Fourmile%20Canyon%20TMP%20w%20attachments.pdf?dl=0>

There was a problem with some of the Dropbox links in the original Bid Document. Please see below for all Dropbox links including corrected links:

Ad Plans

<https://www.dropbox.com/s/dy5sbph5e4wbzxt/Gold%20Run%20Print%20AD%20Set%20Revised-070717.pdf?dl=0>

Special Provisions

[https://www.dropbox.com/s/064zr4of4lfka5j/4043sept12C38 Project%20Special%20Provisions%20 Advertisement 06302017%20-%20REVISED.pdf?dl=0](https://www.dropbox.com/s/064zr4of4lfka5j/4043sept12C38%20Project%20Special%20Provisions%20Advertisement%2006302017%20-%20REVISED.pdf?dl=0)

Revised Final Geotechnical Report

<https://www.dropbox.com/s/ztjtinvevlnllrr/Final%20GeotechnicalReportGoldRun%205-16-17.pdf?dl=0>

Final Pavement Investigation Report

<https://www.dropbox.com/s/9mlm2t0r0ghh6if/Final%20Gold%20Run%20Pavement%20Report.pdf?dl=0>

Quality Assurance Plan

https://www.dropbox.com/s/0pv0us9pl0msmba/Gold%20Run%20QA%20Plan_20170619.pdf?dl=0

ROW Conditions Report

https://www.dropbox.com/s/t4hjevmlshrgfw4/Gold%20Run%20ROW%20Conditions%20Report_V4_Redacted.pdf?dl=0

Also attached is a Bid Tab revised to include separate quantities for Bid Alternate.

Submittal Instructions:

Submittals are due at the Administrative Services Front Desk or the email box (preferred) listed below, for time and date recording on or before **10:00 a.m. Mountain Time on July 28, 2017.**

Your response can be submitted in the following ways. Please note that email responses to this solicitation are preferred, but are limited to a maximum of 25MB capacity. NO ZIP FILES ALLOWED. Electronic Submittals must be received in the e-mail box listed below. Submittals sent to any other box will NOT be forwarded or accepted. This e-mail box is only accessed on the due date of your questions or proposals. Please use the Delivery Receipt option to verify receipt of your email. It is the sole responsibility of the proposer to ensure their documents are received before the deadline specified above. Boulder County does not accept responsibility under any circumstance for delayed or failed email or mailed submittals.

E-Mail purchasing@bouldercounty.org; identified as **BID # 6666-17** in the subject line.

-OR-

US Mail **One (1)** unbound copy of your submittal, printed double-sided, 11 point, on at least 50% post-consumer, recycled paper must be submitted in a sealed envelope, clearly marked as **BID # 6666-17**, to the Administrative Services Front Desk at 2025 14th Street, Boulder, CO 80302.

All proposals must be received and time and date recorded at the Administrative Services Front Desk by the above due date and time. Sole responsibility rests with the Offeror to see that their proposal is received on time at the stated location(s). Any proposal received after due date and time will be returned to the bidder. No exceptions will be made.

The Board of County Commissioners reserve the right to reject any and all proposals, to

waive any informalities or irregularities therein, and to accept the proposal that, in the opinion of the Board, is in the best interest of the Board and of the County of Boulder, State of Colorado.



**RECEIPT OF LETTER
ACKNOWLEDGMENT**

July 11, 2017

Dear Vendor:

This is an acknowledgment of receipt of Addendum #2 for BID #6666-17, Gold Run Road Permanent Repairs and Gold Run Stream Restoration.

In an effort to keep you informed, we would appreciate your acknowledgment of receipt of the preceding addendum. Please sign this acknowledgment and e-mail it back to purchasing@bouldercounty.org as soon as possible. If you have any questions, or problems with transmittal, please call us at 303-441-3525.

Thank you for your cooperation in this matter. This information is time and date sensitive; an immediate response is requested.

Sincerely,

Boulder County Purchasing

Signed by: _____ **Date:** _____

Name of Company _____

End of Document

BOULDER COUNTY TRANSPORTATION DEPARTMENT

ENGINEERING DIVISION

GOLD RUN ROAD PERMANENT REPAIRS AND GOLD RUN STREAM RESTORATION

4043.SEPT12C38

CONTRACT ID #TDST17127F

BID #6666-17

BID ABSTRACT

7/10/2017

INDEX ITEM NO.	ITEM DESCRIPTION	UNIT	UNIT COST	QUANTITY	BID ALT A QUANTITY	TOTAL QUANTITY	TOTAL COST
201-00000	Clearing and Grubbing	LS		1		1	
202-00001	Removal of Structure	EACH		1		1	
202-00001	Removal of Structure (Existing Ped Bridge - 1007 Gold Run Rd)	EACH		1		1	
202-00010	Removal of Tree	LS		1		1	
202-00035	Removal of Pipe	LF		974	54	1028	
202-00090	Removal of Delineator	EACH		54	5	59	
202-00220	Removal of Asphalt Mat	SY		5499	667	6166	
202-01000	Removal of Wood Fence (Post)	LF		1		1	
202-04002	Clean Culvert	EACH		1		1	
202-01130	Removal of Guardrail Type 3	LF		39		39	
202-04001	Plug Culvert	EACH		1		1	
203-00060	Embankment Material (Complete In Place)	CY		6514		6514	
203-00100	Muck Excavation	CY		144	6	150	
203-00400	Rock Excavation	CY		50		50	
203-01500	Blading	HOURL		20		20	
203-01510	Backhoe	HOURL		10		10	
203-01550	Dozing	HOURL		20		20	
203-01594	Combination Loader	HOURL		10		10	
203-02330	Laborer	HOURL		18	2	20	
206-00000	Structure Excavation	CY		3470	106	3576	
206-00100	Structure Backfill (Class 1)	CY		2637	59	2696	
206-00200	Structure Backfill (Class 2)	CY		84		84	
206-00510	Filter Material (Class A)	CY		180		180	
206-01781	Shoring (Area 1)	LS		1		1	
206-01782	Shoring (Area 2)	LS		1		1	
206-01783	Shoring (Area 3)	LS		0	1	1	
206-01784	Shoring (Area 4)	LS		1		1	
206-01785	Shoring (Area 5)	LS		1		1	
206-01786	Shoring (Area 6)	LS		1		1	
206-01787	Shoring (Area 7)	LS		1		1	
206-01788	Shoring (Area 8)	LS		1		1	
207-00205	Topsoil	CY		2664	119	2783	
207-00210	Stockpile Topsoil	CY		2630		2630	
208-00002	Erosion Log (12 Inch)	LF		1675	125	1800	
208-00020	Silt Fence	LF		5305	355	5660	
208-00041	Rock Check Dam	EACH		28	2	30	
208-00045	Concrete Washout Structure	EACH		5	1	6	
208-00070	Vehicle Tracking Pad	EACH		6		6	
208-00103	Removal and Disposal of Sediment (Labor)	HOURL		18	2	20	
208-00105	Removal and Disposal of Sediment (Equipment)	HOURL		18	2	20	
208-00106	Sweeping (Sediment Removal)	HOURL		9	1	10	
208-00207	Erosion Control Manager (ECM)	DAY		72	8	80	
208-00301	Temporary Diversion	LF		618	60	678	
210-00001	Reset Structure	EACH		2		2	
210-00010	Reset Mailbox Structure	EACH		31	4	35	
210-00810	Reset Ground Sign	EACH		26	2	28	
210-01000	Reset Wood Fence	LF		32		32	
211-03005	Dewatering	LS		1		1	
212-00006	Seeding (Native)	ACRE		2.88	0.12	3	
212-00009	Seeding (Temporary)	ACRE		0.3		0.3	
212-00032	Soil Conditioning	ACRE		2.88	0.12	3	
212-01200	Landscape Restoration	LS		1		1	
213-00004	Mulching (Weed Free Straw)	ACRE		2.88	0.12	3	
213-00061	Mulch Tackifier	LB		576	24	600	
214-00000	Landscape Maintenance	LS		1		1	
214-00225	Deciduous Tree (2.5 Inch Caliper)	EACH		23		23	
214-00506	Evergreen Tree (6 Foot) (Ball and Burlap)	EACH		22		22	
216-00022	Soil Retention Blanket (Class 2)	SY		877		877	
216-00303	Turf Reinforcement Mat (Class 3)	SY		1562	198	1760	
217-00020	Herbicide Treatment	HOURL		18	2	20	

INDEX ITEM NO.	ITEM DESCRIPTION	UNIT	UNIT COST	QUANTITY	BID ALT A QUANTITY	TOTAL QUANTITY	TOTAL COST
240-00000	Wildlife Biologist	HOURL		23	2	25	
240-00010	Removal of Nests	HOURL		29	1	30	
304-06007	Aggregate Base Course (Class 6)	CY		2320	126	2446	
403-33821	Hot Mix Asphalt (Grading S) (100) (PG 58-28)	TON		1091	142	1233	
420-00102	Geotextile (Erosion Control) (Class 1)	SY		4129	72	4201	
503-00024	Drilled Caisson (24 Inch)	LF		225	156	381	
504-06315	Ground Nail (15 Foot)	EACH		38		38	
504-08050	Stone Landscape Wall	SF		150		150	
506-00030	Grouted Riprap (Special)	CY		32		32	
506-00209	Riprap (9 Inch)	CY		62	5	67	
506-00212	Riprap (12 Inch)	CY		3	7	10	
506-00236	Riprap (36 Inch)	CY		143		143	
506-00406	Soil Riprap (6 Inch)	CY		165		165	
506-00409	Soil Riprap (9 Inch)	CY		804	61	865	
506-00412	Soil Riprap (12 Inch)	CY		630	119	749	
506-00418	Soil Riprap (18 Inch)	CY		1452	35	1487	
506-00424	Soil Riprap (24 Inch)	CY		502		502	
509-00000	Structural Steel	LB		36327	21610	57937	
601-01000	Concrete Class B	CY		475	9	484	
601-03000	Concrete Class D	CY		19		19	
601-03050	Concrete Class D (Wall)	CY		41.7	20.3	62	
601-40005	Cut Stone Veneer	SF		7854	1314	9168	
601-40008	Cut Stone Veneer (Repair)	SF		45		45	
601-40009	Match and Repair Existing Stone Veneer	LS		10		10	
601-40301	Structural Concrete Coating	SF		3425		3425	
601-40302	Structural Concrete Coating (Anti-Graffiti)	SF		3425		3425	
602-00000	Reinforcing Steel	LB		46190	1480	47670	
602-00020	Reinforcing Steel (Epoxy Coated)	LB		6320	3029	9349	
603-01185	18 Inch Reinforced Concrete Pipe (Complete In Place)	LF		387		387	
603-01245	24 Inch Reinforced Concrete Pipe (Complete In Place)	LF		55		55	
603-01305	30 Inch Reinforced Concrete Pipe (Complete In Place)	LF		55		55	
603-01365	36 Inch Reinforced Concrete Pipe (Complete In Place)	LF		22		22	
603-01425	42 Inch Reinforced Concrete Pipe (Complete In Place)	LF		31	82	113	
603-01485	48 Inch Reinforced Concrete Pipe (Complete In Place)	LF		56		56	
603-01785	78 Inch Reinforced Concrete Pipe (Complete In Place)	LF		241		241	
603-02180	23x14 Inch Reinforced Concrete Pipe Elliptical	LF		14		14	
603-02245	30x19 Inch Reinforced Concrete Pipe Elliptical (Complete In Place)	LF		48	77	125	
603-02720	91x58 Inch Reinforced Concrete Pipe Elliptical	LF		54		54	
603-02780	98x63 Inch Reinforced Concrete Pipe Elliptical	LF		28		28	
603-05018	18 Inch Reinforced Concrete End Section	EACH		20		20	
603-05024	24 Inch Reinforced Concrete End Section	EACH		4		4	
603-05030	30 Inch Reinforced Concrete End Section	EACH		32		32	
603-05036	36 Inch Reinforced Concrete End Section	EACH		2		2	
603-05042	42 Inch Reinforced Concrete End Section	EACH		2		2	
603-05048	48 Inch Reinforced Concrete End Section	EACH		2		2	
603-05118	23x14 Inch Reinforced Concrete End Section Elliptical	EACH		2		2	
603-05124	30x19 Inch Reinforced Concrete End Section Elliptical	EACH		0	4	4	
603-70704	7x4 Foot Concrete Box Culvert (Precast)	LF		0	24	24	
603-70804	8x4 Foot Concrete Box Culvert (Precast)	LF		61		61	
603-70805	8x5 Foot Concrete Box Culvert (Precast)	LF		230		230	
603-70806	8x6 Foot Concrete Box Culvert (Precast)	LF		66		66	
604-30010	Manhole Slab Base (10 Foot)	EACH		1		1	
606-00301	Guardrail Type 3 (6-3 Post Spacing)	LF		38		38	
606-00306	NatureRail Guardrail (6'-6-3/4" Post Spacing)	LF		20		20	
606-00307	NatureRail Guardrail Drop Down End Terminal (19'-8-3/4")	EACH		4		4	
606-01390	End Anchorage Type 3K	EACH		10		10	
606-02001	FHWA G4-W Beam Type LST End Terminal	EACH		1		1	
606-02005	End Anchorage (Flared)	EACH		3		3	
607-11525	Fence (Plastic)	LF		535		535	
609-23000	Gutter (Special)	LF		16		16	
609-24004	Gutter Type 2 (4 Foot)	LF		163		163	
612-00001	Delineator (Type I)	EACH		284	26	310	
612-00003	Delineator (Type III)	EACH		35	3	38	
613-01302	3 Inch Electrical Conduit (Plastic) (Install Only)	LF		170		170	
614-00011	Sign Panel (Class I)	SF		100.5	10.5	111	
614-01502	Steel Sign Support (2-Inch Round)(Post & Socket)	LF		380	44	424	
619-50320	4 Inch Plastic Pipe	LF		100		100	

INDEX ITEM NO.	ITEM DESCRIPTION	UNIT	UNIT COST	QUANTITY	BID ALT A QUANTITY	TOTAL QUANTITY	TOTAL COST
619-50481	6 Inch Plastic Pipe (Install Only)	LF		170		170	
620-00002	Field Office (Class 2)	EACH		2		2	
620-00020	Sanitary Facility	EACH		4		4	
625-00000	Construction Surveying	LS		1		1	
626-00000	Mobilization	LS		1		1	
627-00001	Pavement Marking Paint	GAL		17	4	21	
630-99997	Traffic Control (Suggested Phasing)	LS		1		1	
641-10000	Shotcrete	SY		86		86	
SUBTOTAL →							
700-70586	F/A Mine Waste Management	FA					\$20,000
630-00002	F/A Uniform Traffic Control	FA					\$25,000
700-70010	F/A Minor Contract Revisions	FA					\$500,000
700-70380	F/A Erosion Control	FA					\$50,000
SUBTOTAL →							\$595,000
ROAD CONSTRUCTION SUBTOTAL →							
Stream Restoration							
201-00001	Clearing and Grubbing	ACRE		1.4		1.4	
202-00010	Removal of Tree	LS		1		1	
203-00041	Unclassified Excavation (Complete in Place)	CY		3097		3097	
203-00042	Stream and Floodplain Grading (Final)	HR		129		129	
208-00400	Water Control	LS		1		1	
212-00023	Revegetation - Riparian Seeding & Mulch	ACRE		1.4		1.4	
214-00156	Revegetation - Zone A (10 CI, Furnish and Install)	EA		209		209	
214-00157	Revegetation - Zone A (10 CI, Install Only)	EA		209		209	
214-00158	Revegetation - Zone A (10 CI, Furnish Only)	EA		957		957	
214-00159	Revegetation - Zone B (40 CI,Furnish and Install)	EA		1145		1145	
214-00160	Revegetation - Zone B (40 CI, Install Only)	EA		1145		1145	
214-00161	Revegetation - Zone B (40 CI, Furnish Only)	EA		468		468	
214-00162	Revegetation - Zone B (3' Cuttings,Furnish and Install)	EA		740		740	
214-00163	Revegetation - Zone B (3' Cuttings, Install Only)	EA		740		740	
214-00164	Revegetation - Zone B (5' Cuttings, Furnish Only)	EA		1134		1134	
214-00165	Revegetation - Zone C (40 CI, Furnish and Install)	EA		400		400	
214-00166	Revegetation - Zone C (40 CI, Install Only)	EA		400		400	
216-00201	Soil Retention Blanket (Straw-Coconut) (Biodegradable Class 1)	SY		2247		2247	
506-00209	Riprap (9 Inch - Type VL)	CY		1430		1430	
506-00212	Riprap (18 Inch - Type H)	CY		51		51	
506-00218	Riprap (24 Inch - Type VH)	CY		42		42	
506-03001	Boulder	CY		2064		2064	
506-03002	On-Site Boulder	CY		685		685	
506-03005	Log (15ft)	EA		45		45	
506-03006	On-Site Log (15ft)	EA		15		15	
506-03007	Root Wad	EA		39		39	
506-03008	On-Site Root Wad	EA		13		13	
506-03009	Soil Wrapped Lift	LF		85		85	
506-03010	Toe Wood	LF		85		85	
506-03012	Geotextile	SY		4452		4452	
506-03014	Root Wad Bank Protection (Installation)	LF		153		153	
506-03015	Toe Wood with Soil Wrapped Lift (Installation)	LF		85		85	
506-03016	Boulder Toe Protection (Installation)	LF		588		588	
506-03017	Stacked Boulder Wall (Installation)	LF		2598		2598	
506-03018	Retaining Wall Toe Protection (Installation)	LF		415		415	
506-03019	Rock Cross Vane (Installation)	EA		1		1	
506-03020	Boulder J-Hook Vane (Installation)	EA		2		2	
506-03021	Converging Boulder Cluster (Installation)	EA		5		5	
506-03022	Rock Step Pool - One Pool with Step Crest (Install Only)	EA		11		11	
506-03023	Culvert Outlet Protection	EA		2		2	
625-00003	Construction Surveying	MILE		1		1	
626-00000	Mobilization	LS		2		2	
630-00005	Traffic Control	LS		2		2	
STREAM SUBTOTAL →							
CONSTRUCTION TOTAL →							