



**ADDENDUM #2**  
**Boulder County Parks and Open Space**  
**Anne U White Trailhead Reconstruction and Stream Stabilization**  
**BID # 7051-19**

August 1, 2019

**Please note: This Addendum includes a revised Bid Tab with a signature block that replaces the one in Addendum 1. Please submit this Bid Tab with your proposal.**

The attached addendum supersedes the original Information and Specifications regarding BID # 7051-19 where it adds to, deletes from, clarifies or otherwise modifies. All other conditions and any previous addendums shall remain unchanged.

**Submittal Instructions:**

BIDs are due at the Administrative Services Information Desk or email box (preferred) listed below, for time and date recording on or before **2:00 p.m. Mountain Time on August 8, 2019**. A bid opening will be conducted at 3:00 p.m. Mountain Time at county offices.

**Your response can be submitted in the following ways. Please note that email responses to this solicitation are preferred, but are limited to a maximum of 50MB capacity. NO ZIP FILES ALLOWED. Electronic Submittals must be received in the email box listed below. Submittals sent to any other box will NOT be forwarded or accepted. This email box is only accessed on the due date of your questions or proposals. Please use the Delivery Receipt option to verify receipt of your email. It is the sole responsibility of the proposer to ensure their documents are received before the deadline specified above. Boulder County does not accept responsibility under any circumstance for delayed or failed email or mailed submittals.**

**Email**        [purchasing@bouldercounty.org](mailto:purchasing@bouldercounty.org); identified as **BID # 7051-19** in the subject line.

-OR-

**US Mail**     **One (1)** unbound copy of your submittal, printed double-sided, 11 point, on at least 50% post-consumer, recycled paper must be submitted in a sealed envelope, clearly marked as **BID # 7051-19**, to the **Administrative Services Information Desk located at 1325 Pearl Street, Boulder, CO 80302**.

All bids must be received and time and date recorded at the Administrative Services Information Desk by the above due date and time. Sole responsibility rests with the Offeror to see that their bid is received on time at the stated location(s). Any bid received after due date and time will be returned to the bidder. No exceptions will be made.

The Board of County Commissioners reserve the right to reject any and all bids, to waive any informalities or irregularities therein, and to accept the bid that, in the opinion of the Board, is in the best interest of the Board and of the County of Boulder, State of Colorado.



**RECEIPT OF LETTER  
ACKNOWLEDGMENT**

August 1, 2019

Dear Vendor:

This is an acknowledgment of receipt of Addendum #2 for BID #7051-19, Anne U White Trailhead Reconstruction and Stream Stabilization.

In an effort to keep you informed, we would appreciate your acknowledgment of receipt of the preceding addendum. Please sign this acknowledgment and email it back to [purchasing@bouldercounty.org](mailto:purchasing@bouldercounty.org) as soon as possible. If you have any questions, or problems with transmittal, please call us at 303-441-3525.

Thank you for your cooperation in this matter. This information is time and date sensitive; an immediate response is requested.

Sincerely,

Boulder County Purchasing

**Signed by:** \_\_\_\_\_ **Date:** \_\_\_\_\_

**Name of Company** \_\_\_\_\_

End of Document

## ATTACHMENT E

### BID# 7051-19; Boulder County Parks and Open Space Anne U White Trailhead Reconstruction and Stream Stabilization

| <b>BID TAB</b>  |   |              |  |                 |                  |                   |
|-----------------|---|--------------|--|-----------------|------------------|-------------------|
| <b>Item No.</b> | <b>Description</b>  | <b>Units</b> |  | <b>Quantity</b> | <b>Unit Cost</b> | <b>Total Cost</b> |
| 1               | Mobilization  | LS           |  | 1               |                  |                   |
| 2               | Clear, grub and protection of designated vegetation   | AC           |  | 0.2             |                  |                   |
| 2.1             | Tree Removal: 30' tall Spruce   | LS           |  | 1               |                  |                   |
| 2.2             | Tree Removal: 20' tall Aspen  | LS           |  | 1               |                  |                   |
| 2.3             | Tree Removal: 12' tall bunch of small Aspen Trees   | LS           |  | 1               |                  |                   |
| 2.4             | Tree Removal: 25' tall Pine   | LS           |  | 1               |                  |                   |
| 3               | Earthwork Cut   | CY           |  | 1,286           |                  |                   |
| 4               | Furnish/ Install fill on top of rock retaining wall (fill at 2H: 1V slope in 9" loose lifts).                   | CY           |  | 76              |                  |                   |
| 5               | Erosion and Sediment Control including maintaining and removing SWMP BMPs                                       | LS           |  | 1               |                  |                   |
| 6               | Furnish/ Install Soil Lifts   | SF           |  | 294             |                  |                   |
| 6.1             | Furnish/ Install Road Base (75/25 Road Base/ Topsoil Mix)   | CY           |  | 45              |                  |                   |
| 6.2             | Furnish/ Install Top Soil ( 75/25 Road Base/ Top Soil Mix)  | CY           |  | 15              |                  |                   |
| 7               | Furnish/ Install 48" Boulder Retaining Wall North Side of the Parking Lot. Includes installation of bedding.    | LF           |  | 120             |                  |                   |
| 8               | Furnish/ Install 18" PIP Culvert (PIP to be supplied and delivered by Owner)                                    | LF           |  | 105             |                  |                   |
| 9               | Furnish/ Install Squeegee PIP bedding   | CY           |  | 21              |                  |                   |
| 10              | Furnish/ Install 12" Riprap Toe for Soil Lifts  | CY           |  | 100             |                  |                   |
| 11              | Furnish/ Install Type II Bedding under Riprap   | CY           |  | 200             |                  |                   |
| 12              | Furnish/ Install Inlet to PIP Culvert   | LS           |  | 1               |                  |                   |
| 13              | Furnish/ Install Outlet to PIP Culvert  | LS           |  | 1               |                  |                   |
| 14              | Furnish/ Install 12"- 24" rock toe upstream of soil lifts (material onsite)                                     | CY           |  | 9               |                  |                   |
| 15              | Haul and Dispose of Excess Soil   | CY           |  | 1,023           |                  |                   |
| 16              | Parking Lot   |              |  |                 |                  |                   |
| 16.1            | Install Snap Cut Lyons Red Sandstone Curbing (supplied and delivered by Owner).                                 | LF           |  | 400             |                  |                   |
| 16.2            | Non-structural concrete   | CY           |  | 12              |                  |                   |
| 16.3            | Class 6 Road Base for parking lot and curb base (supplied by Owner. Contractor responsible for haul - 16 miles) | CY           |  | 369*            |                  |                   |
| 16.4            | Install 20 Delineator Boulders (material onsite)  | LS           |  | 1               |                  |                   |
| 17              | Furnish/ Install Creek Check Dam  | CY           |  | 0.56            |                  |                   |
| 18              | Import and Install top soil   | CY           |  | 180*            |                  |                   |
| 19              | Install fill (Onsite Material)  | CY           |  | 64              |                  |                   |

