Boulder County Purchasing
1325 Pearl Street
Boulder, CO 80302
purchasing@bouldercounty.org

BID WORKSHEET TABLE

Revision 5/21/2020

BID ITEM	BID ITEM CODE	Related Technical Spec	DESCRIPTION	QUANTITY	PAY UNIT	UNIT PRICE	TOTAL COST OF BID ITEM
General							
1	GN-01-001	31 11 00	Clearing and Grubbing	3.2	AC		
2	GN-02-001	01 71 13	Mobilization	1	LS		
3	GN-04-001	01 71 23	Survey - Construction	1	LS		
4	GN-04-002	01 71 23	Survey - As Built	1	LS		
5	GN-05-001	01 55 26	Traffic Control	1	LS		
6	GN-06-001	31 23 19	Water Control	1	LS		
Erosion and Sediment Control							
7	ESC-01-001	31 25 00	General BMP Maintenance	115	HR		
8	ESC-03-001	31 25 00	Check Dam	28	CY		
9	EC-10-001	31 25 00	Rock Socks	0	LF		
10	ESC-13-001	31 25 00	Sediment Control Log	1499	LF		
11	ESC-15-001	31 25 00	Silt Fence	0	LF		
12	ESC-17-002	31 25 00	Stabilized Staging Area	8091	SY		
13	ESC-17-002	31 25 00	Modified Stabilized Staging Areas: Note 2	1217	SY		
14	ESC-19-002	31 25 00	Stream Crossing, Temporary (culvert)	1	EA		
15	ESC-20-001	31 25 00	Vehicle Tracking Control	1	EA		
16	ESC-22-001	01 56 39	Tree Protection, Fence	1800	LF		
Earthwork and Subgrade Prep							
17	ESP-02-001	31 23 00	Earthwork, Excavation and Fill On-Site	1200	CY		
18	ESP-02-002	31 23 00	Earthwork, Excavation and Haul Off-Site: Note 1	5790	CY		
19	ESP-06-004	31 23 00	Excavation, Rock, Stockpile, and Reuse (Boulders and Channel Bed Material)	770	CY		
20	ESP-07-001	207	Topsoil Excavate, Stockpile, and Replace	1637	CY		

21	ESP-07-002	207	Topsoil-Wetland Excavate, Stockpile, and Replace	540	CY		
22	ESP-09-001	31 23 00	Fine Floodplain Grading	10807	SY		
23	ESP-09-002	31 23 00	Fine Channel Grading	4387	SY		
Remove, Relocate, and Abandon							
24	RR-06-001	31 23 00	Remove Structures and Obstructions (trash and flood debris)	1	LS		
25	RR-06-018	31 11 00	Remove Tree - Large Tree (Greater than 1-ft diameter or multi-stem)	20	EA		
Rockwork							
26	RW-11-004	31 37 00	Void-Filled Riprap, Type H (Bypass Structure)	1529	CY		
27	RW-10-003	31 37 00	Type M Riprap (Bypass Structure)	169	CY		
28	RW-11-001	31 37 00	Void-Filled Riprap with River Cobble, Type VL (Fish Passage Channel Riffles)	575	CY		
29	RW-06-001	31 37 00	Boulder, Feature (B18 - Habitat)	105	EA		
30	RW-06-002	31 37 00	Boulder, Feature (B24 - Habitat)	246	EA		
31	RW-12-003	31 37 00	Soil Riprap, Type M (Breach Slope)	903	CY		
32	RW-13-001	31 37 00	Cobbles, Import Type M (Riffle Crests)	52	CY		
Structures and Misc. Concrete							
33	SC-18-001	31 62 16	Sheet Pile, Steel, Heavy	1560	SF		
34	UC-02-001	13 50 01	Stop Log Bays: Note 3	1	LS		
Fencing							
35	FN-01-004	32 31 00	Fence, Construction - Staging and access area	7110	LF		
Landscaping							
36	LS-02-004	216	Erosion Control Fabric (Coir)	1890	SY		
37	LS-02-004	216	Erosion Control Blanket (Straw-Coconut)	4180	SY		
38	LS-07-001	213	Spray-on Hydromulch (Upland-Riparian)	2	AC		
39	LS-07-001	213	Spray-on Hydromulch (Wetland)	1.1	AC		
40	LS-10-006	212	Upland Seeding: Note 4	2	AC		
41	LS-10-008	212	Wetland Seeding: Note 4	1.1	AC		
42	LS-11-003	214	Upland Trees and Shrubs (14" tall 1-gal.): Note 4	66	EA		
43	LS-11-003	214	Riparian Trees and Shrubs (14" tall 1-gal.): Note 4	1156	EA		
44	LS-20-001	214	Wetland Trees and Shrubs (14" tall 1-gal.): Note 4	584	EA		

45	LS-14-004	214	Willow Stakes (48" cuttings): Note 4	5260	EA		
46	LS-21-001	215	Wetland Tree/Shrub Clump Transplants: Note 4	300	EA		
47	LS-21-002	215	Riparian/Upland Tree/Shrub Clump Transplants: Note 4	10	EA		
48	UC-03-001	212	Topsoil Conditioning (Compost, Upland – Riparian, 3 CY/1000 SF)	2	AC		
49	UC-03-002	212	Topsoil Conditioning (Compost, Wetland, 6CY/1000 SF)	1.1	AC		
50	UC-03-003	212	Topsoil Conditioning (Biotic Soil Media)	1	AC		
51	UC-03-004	212	Topsoil Conditioning (Fertilizer and Additives)	1	AC		
Unclassified							
52	UC-04-001	13 40 01	Rootwad Log Installed	6	EA		
53	UC-04-002	13 40 01	Small Wood Habitat Feature Installed	7	CY		

BID TOTAL $_____

NOTES

1 Excess clean cut material hauled to 5201 St Vrain Rd, Longmont, CO 80503

2 Modified stabilized staging areas include the two smaller staging areas in close proximity to the bypass structure, where only stockpile stabilization and perimeter silt fencing is necessary

3 Stop log bays cost includes hardware for the bays and catwalk, grouted boulders, and grout washout area, but does not include sheet pile and rock for remaining structure (included as separate pay items)

4 Landscape construction and establishment maintenance cost (weed control and irrigation) for 120 days after installation are included in unit cost of bid items 40 through 47. Warranty work beyond this time frame should be minimal if specifications are followed, but recommendations for the warranty period beyond the establishment period are also included in the specifications.